

# Project Reference

## Lincolnshire County Council Gainsborough

### :: Installation requirements

When Lincolnshire County Council decided to move to new offices in Gainsborough they asked Trent Valley Construction to find a decorative hardwearing floor finish in the reception area. The Council were looking for an attractive, yet hardwearing floor to welcome guests into their new premises. As a focal point of the new development aesthetics were a top priority.

### :: Why National Flooring?

Following meetings with Trent Valley Construction it became clear that the Degaflor Flake System was the ideal solution to match the Council's specification. The system, which offers enormous flexibility in terms of aesthetics, provided the Council with the opportunity to create an eye-catching design. The client chose a grey finish with black flakes and silver glitter to complement the surroundings.

The system, which is installed at a nominal thickness of 4mm, provides outstanding durability which is required in this high footfall area. The floor is easy to clean and maintain, again making it the ideal solution for a reception area.

Prior to installing the Degaflor Flake System, National Flooring was required to lay a polymer screed to level out the floor before applying the resin finish. Working with Trent valley Construction, National Flooring was able to complete the entire installation with minimal disruption to ensure that the development could progress within the limited timescales.



**NATIONAL FLOORING**  
Floors For Industry



The National Flooring Company Ltd  
Crusader House  
High Street  
Maxey  
Peterborough  
PE6 9HQ  
UK  
T:01778 343670 F:01778 380912  
W: [www.nationalflooring.co.uk](http://www.nationalflooring.co.uk)  
E: [enquiries@nationalflooring.co.uk](mailto:enquiries@nationalflooring.co.uk)